BRUHAT BANGALORE MAHANAGARA PALIKE

Modified Schedule-B

Name of the work: Sub Estimate for Providing water supply through pipeline to Existing Borewells in ward no. 08 Kodigehalli.

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	60	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications,	cum	288.36	Rupees Two Hundred Eighty Eight and Thirty Six Paise Only
2	3200.00	Supplying PVC ring ting pipes comforming to IS 4985:2000 with latest amendments and conveying to worksite rolling and lowering into trenches laying true line and level and perfect lingking at joints testing and commissioning including loading and unlowading at both destination and cuts of pipes whereever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approval type with all labour with all lead and lift incluidng encasing the pipe alround to a depth of not less than 15cms with soft gravel or selected earth avilable from the excavation etc., compelete and giving necessary hydraluic test to the reuired pressure as per IS (contractor will make his own arrangement for procuring water for testing	Rmtr	77.38	Rupees Seventy Seven and Thirty Eight Paise Only
3	59.74	Refilling avilable earth earth around pipe lines, cables in layers not exceeding 2cms in depth, compacting each deposited layer by ramming ater watering with lead upto 50mm and lift upto 1.5m including cost of all labour complete as per specifications allow 60% of rate considered under item	cum	77.76	Rupees Seventy Seven and Seventy Six Paise Only
4	26.55	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density. Material (Table 400-11) Clause: 406 PWD SR 2008-09 (P.141/I.19.16)	cum	1713.96	Rupees One Thousand Seven Hundred Thirteen and Ninety Six Paise Only
5	3.98	KSRRB M500-15: Providing and laying bituminous concrete using 100/120 THP capacity HMP with sensor paver Gr-II (30mm to 45mm), crushed aggregates of specified grading premixed with 6% CRMB 55grade bituminous binder and transporting the hot mix to work site, laying to the required level and grade, rolling transporting the hot mix to work site, laying to the required level and grade, rolling with wheeled, ivbratory and tandeem rollers to achieve the desired density including all leads and lift cost of all materials, labour, HOM of machineries complete as per specifications	cum	9888.48	Rupees Nine Thousand Eight Hundred Eighty Eight and Forty Eight Paise Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore Mahanagara Palike and as directed.
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'. 07/04

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

CONTRACTOR